SITE WEATHER · JEDDAH · FRIDAY 20 NOVEMBER

Pour concrete 07-11 h; fast drying limits the rest of the day.

Rain 0 mm · 12% | Storms low | Heat 29 °C WBGT | Gusts 12 m/s

OUTDOOR LABOUR

Limited — **Work/rest cycles**

07	08	09	10	11	13	14	15	16
Limited	Limited	Limited	Limited	Limited	Go	Go	Go	Go

Work/rest cycles 09-12 h, 13-17 h: at the peak, 30 min work / 30 min rest. Water every 20 min, shade for breaks.

CONCRETE POUR

Limited — **Go 07-11 h, 16-17 h**

07	08	09	10	11	13	14	15	16
Limited	Limited	Limited	Limited	Limited	Go	Go	Go	Go

Limited by fast drying. Curing cover and windbreaks ready.

ASPHALT & SURFACING

Limited — **Go 08-12 h, 13-17 h**

07	08	09	10	11	13	14	15	16
Limited	Go	Go	Go	Go	Go	Go	Go	Go

Limited by rain or wet surface. Never lay or spray on a wet surface.

PAINTING & COATINGS

Limited — **Go 08-12 h, 13-17 h**

07	08	09	10	11	13	14	15	16
Stop	Go	Go	Go	Go	Go	Go	Go	Go

Limited by humidity or dew. Check the surface is 3 °C above dew point.

NO WEATHER LIMITS

Go

Crane lifts, Work at height, Earthworks.

Screening guidance from a forecast. Your contract, crane limits and site H&S plan come first.

gavacharles.github.io/kampala-heat-atlas/site-weather/jeddah

By Gava Charles · Kampala Heat Atlas · forecast data Open-Meteo

SITE WEATHER · JEDDAH

The week on site

When each trade can go ahead, 07-17 h, lunch excluded

	Fri 20	Sat 21	Sun 22	Mon 23	Tue 24	Wed 25	Thu 26
Outdoor labour	07-09	07-09	07-10	07-10 16-17	07-10 16-17	07-10 14-17	07-11 13-14+
Concrete pour	07-11 16-17	07-12	07-12	07-12 16-17	07-12 16-17	07-12	07-12 13-14
Asphalt & surfacing	08-12 13-17	all day	07-12	all day	all day	all day	all day
Crane lifts	all day	all day	07-12 13-14	all day	all day	all day	all day
Work at height	all day	all day	07-12 13-14	all day	all day	all day	all day
Painting & coatings	08-12 13-17	09-12 13-17	09-12 13-14	08-12 13-17	08-12 13-17	all day	all day
Earthworks	all day	all day	07-12 13-14+	all day	all day	all day	all day
Rain	0 mm 12%	0 mm 14%	2 mm 75%	0 mm 4%	0 mm 6%	0 mm 2%	0 mm 4%
Storms	low	low	possible	low	low	low	low

go most of the day · part of the day · little or none

Times are go windows: 08-13 = from 08:00 until the lunch break; + = more windows that day.

Screening guidance from a forecast. Your contract, crane limits and site H&S plan come first.

gavacharles.github.io/kampala-heat-atlas/site-weather/jeddah

By Gava Charles · Kampala Heat Atlas · forecast data Open-Meteo

SITE WEATHER · HOW IT WORKS

How to read the cards

A daily weather check for contractors and site managers

STEP 01 · 1

The headline

The one thing to plan the day around. The key time is marked in yellow.

STEP 02 · 2

A card per trade

Problems first: Stop, Limited (go only in the hours shown), Care. Trades with no limits share one card.

STEP 03 · 3

Hour chips

9 working hours, 07:00-17:00, lunch excluded. Green go, amber care, red stop.

STEP 04 · 4

Heat uses WBGT

The standard for heat stress at work; it sets work/rest cycles.

STEP 05 · 5

Concrete and asphalt

Rain now or within three hours, wet surfaces, and drying fast enough to crack fresh concrete (ACI 305).

STEP 06 · 6

Cranes and painting

Gusts at 30 m hook height and storms; painting needs the surface 3 °C above dew point (ISO 8502-4).

STEP 07 · 7

Every day on record

Month by month against the 1991-2020 climate, for programme reviews and delay claims.

Screening guidance from a forecast. Your contract, crane limits and site H&S plan come first.

gavacharles.github.io/kampala-heat-atlas/site-weather/jeddah

By Gava Charles · Kampala Heat Atlas · forecast data Open-Meteo